


AD-A100 406

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/G 13/13  
NATIONAL DAM SAFETY PROGRAM. CRYSTAL LAKE DAM (NJ00299), DELAWARE--ETC(U)  
JUN 81 R J MCDERMOTT, J E GRIBBIN DACW61-79-C-0011

UNCLASSIFIED

DAEN/NAP-53842/NJ00299-81/ NL

1 OF 1  
AD A  
FOC 406



END  
DATE  
FILMED  
7-81  
DTIC

AD A100400

DELAWARE RIVER BASIN  
TRIBUTARY TO DELAWARE RIVER  
BURLINGTON COUNTY  
NEW JERSEY.

National Dam Safety Program.

CRYSTAL LAKE DAM

NJ00299

LEVEL II

DTIC  
ELECTE  
JUN 19 1980

PHASE I INSPECTION REPORT.  
NATIONAL DAM SAFETY PROGRAM

15) DACW61-79-C-8011

9) Final rep.  
10) Richard J. McDermott  
John E. Gribbin

14) Jun 81 12) 78

APPROVED FOR PUBLIC RELEASE  
DISTRIBUTION UNLIMITED.

DEPARTMENT OF THE ARMY

Philadelphia District  
Corps of Engineers  
Philadelphia, Pennsylvania


Dist. # 100-103374 174/27-81/4

JUNE 1981

48791 81-6-18 032-2

| REPORT DOCUMENTATION PAGE  |                                       | READ INSTRUCTIONS<br>BEFORE COMPLETING FORM                    |
|--|---------------------------------------|--|
| 1. REPORT NUMBER<br>DAEN/NAP-53842/NJ00299-81/06   | 2. GOVT ACCESSION NO.<br>AD-A100 4106 | 3. RECIPIENT'S CATALOG NUMBER                                  |
| 4. TITLE (and Subtitle)<br>Phase I Inspection Report<br>National Dam Safety Program<br>Crystal Lake Dam, NJ00299<br>Burlington County, NJ  |                                       | 5. TYPE OF REPORT & PERIOD COVERED<br>FINAL                    |
| 7. AUTHOR(s)<br>McDermott, Richard J., P.E.<br>Gribbin, John E., P.E.  |                                       | 6. PERFORMING ORG. REPORT NUMBER                               |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS<br>Storch Engineering<br>220 Ridgedale<br>Florham Park, N.J. 07932   |                                       | 8. CONTRACT OR GRANT NUMBER(s)<br>DACW61-79-C-0011 /           |
| 11. CONTROLLING OFFICE NAME AND ADDRESS<br>NJ Department of Environmental Protection<br>Division of Water Resources<br>P.O. Box CNO29<br>Trenton, NJ 08625   |                                       | 10. PROGRAM ELEMENT, PROJECT, TASK<br>AREA & WORK UNIT NUMBERS |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)<br>U.S. Army Engineer District, Philadelphia<br>Custom House, 2d & Chestnut Streets<br>Philadelphia, PA 19106  |                                       | 12. REPORT DATE<br>June, 1981                                  |
|  |                                       | 13. NUMBER OF PAGES<br>50                                      |
|  |                                       | 15. SECURITY CLASS. (of this report)<br>Unclassified           |
|  |                                       | 15a. DECLASSIFICATION/DOWNGRADING<br>SCHEDULE                  |
| 16. DISTRIBUTION STATEMENT (of this Report)<br>Approved for public release; distribution unlimited.  |                                       |  |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)   |                                       |  |
| 18. SUPPLEMENTARY NOTES<br>Copies are obtainable from National Technical Information Service,<br>Springfield, Virginia 22151.  |                                       |  |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number)<br>Dams<br>Embankments<br>Visual Inspection<br>Structural Analysis<br>National Dam Safety Program<br>Crystal Lake Dam, NJ<br>Riprap<br>Outlet works   |                                       |  |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number)<br>This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report. |                                       |  |

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

NOTICE

THIS DOCUMENT HAS BEEN REPRODUCED  
FROM THE BEST COPY FURNISHED US BY  
THE SPONSORING AGENCY. ALTHOUGH IT  
IS RECOGNIZED THAT CERTAIN PORTIONS  
ARE ILLEGIBLE, IT IS BEING RELEASED  
IN THE INTEREST OF MAKING AVAILABLE  
AS MUCH INFORMATION AS POSSIBLE.

Z H F P ( Y H E F F T ) \* ( )

 $\text{N-M'N-N}$ 

DEPARTMENT OF THE ARMY  
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS  
CUSTOM HOUSE-2 D & CHESTNUT STREETS  
PHILADELPHIA, PENNSYLVANIA 19106

|                               |         |
|-------------------------------|---------|
| Accession For                 |         |
| NTIS GRA&I                    |         |
| DUC TAB                       |         |
| Unconnected<br>Classification |         |
|                               |         |
|                               |         |
|                               |         |
| File Number /                 |         |
| Availability                  |         |
| or location                   |         |
| List                          | Special |
| A                             |         |

5 JUN 1960

honorable Brendan T. Byrne  
Governor of New Jersey  
Trenton, New Jersey 08621

APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED.

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Crystal Lake Dam in Burlington County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Crystal Lake Dam, initially listed as a high hazard potential structure, but reduced to a significant hazard potential structure as a result of this inspection is judged to be in good overall condition and the spillway is considered adequate. To ensure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The following actions should be initiated within six months from the date of approval of this report:

- (1) The outlet works should be investigated with respect to operational adequacy and, if necessary, restored to proper operational condition.
- (2) Rusted CMP surface drain pipe should be replaced by proper inlet and pipe.
- (3) Erosion of the embankment adjacent to the upstream wingwalls of the bridge should be properly stabilized.
- (4) Deteriorating riprap on the upstream and downstream faces of embankment should be repaired where necessary.
- (5) All trees and adverse vegetation on the embankment should be removed.

NAPEN-N

Honorable Brendan T. Byrne

b. The owner should develop an emergency action plan together with an effective warning system outlining actions to be taken by the operator to minimize downstream effects of an emergency at the dam within six months from the date of approval of this report.

c. The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam within one year from the date of approval of this report.

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman Smith of the Fourth District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Inspection Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,



KENNETH R. MOSER

Major, Corps of Engineers

Acting Commander and District Engineer

1 Incl

As stated

Copies furnished:

Mr. Dirk C. Hofman, P.E., Deputy Director  
Division of Water Resources  
N.J. Dept. of Environmental Protection  
P.O. Box CN029  
Trenton, NJ 08625

Mr. John O'Dowd, Acting Chief  
Bureau of Flood Plain Regulation  
Division of Water Resources  
N.J. Dept. of Environmental Protection  
P.O. Box CN029  
Trenton, NJ 08625

CRYSTAL LAKE DAM (NJD00299)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 6 January 1981 by Storch Engineers, under contract to the State of New Jersey. The State, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-597.

Crystal Lake Dam, initially listed as a high hazard potential structure, but reduced to a significant hazard potential structure as a result of this inspection is judged to be in good overall condition and the spillway is considered adequate. To ensure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The following actions should be initiated within six months from the date of approval of this report:

(1) The outlet works should be investigated with respect to operational adequacy and, if necessary, restored to proper operational condition.

(2) Rusted CMP surface drain pipe should be replaced by proper inlet and pipe.

(3) Erosion of the embankment adjacent to the upstream wingwalls of the bridge should be properly stabilized.


(4) Deteriorating riprap on the upstream and downstream faces of embankment should be repaired where necessary.

(5) All trees and adverse vegetation on the embankment should be removed.

b. The owner should develop an emergency action plan together with an effective warning system outlining actions to be taken by the operator to minimize downstream effects of an emergency at the dam within six months from the date of approval of this report.

c. The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam within one year from the date of approval of this report.

APPROVED:

  
KENNETH R. MOSER  
Major, Corps of Engineers  
Acting Commander and District Engineer

DATE:

4 June 1981



PHASE I REPORT  
NATIONAL DAM SAFETY REPORT

|                     |                                |
|---------------------|--------------------------------|
| Name of Dam:        | Crystal Lake Dam, I.D. NJ00299 |
| State Located:      | New Jersey                     |
| County Located:     | Burlington                     |
| Drainage Basin:     | Delaware River                 |
| Stream:             | Tributary to Delaware River    |
| Date of Inspection: | January 6, 1981                |

Assessment of General Condition of Dam

Based on visual inspection, past operational performance and Phase I engineering analyses, Crystal Lake Dam is assessed as being in good overall condition.

Based on investigations of the downstream flood plain made in connection with this report, it is recommended that the hazard potential classification be downgraded from high to significant hazard.

The spillway is capable of passing the designated spillway design flood (100-year storm) without an overtopping of the dam and, therefore, is assessed as being adequate.


The owner should, in the near future, develop an emergency action plan together with an effective warning system outlining actions to be taken by the operator to minimize downstream effects of an emergency at the dam.


In addition, it is recommended that the following remedial measures be undertaken by the owner in the near future.

- 1) The outlet works should be investigated with respect to operational adequacy and, if necessary, restored to proper operational condition.

- 2) Rusted CMP surface drain pipe should be replaced by proper inlet and pipe.
- 3) Erosion of the embankment adjacent to the upstream wingwalls of the bridge should be properly stabilized.
- 4) Deteriorating riprap on the upstream and downstream faces of embankment should be repaired where necessary.
- 5) All trees and adverse vegetation on the embankment should be removed.

In the future, the owner of the dam should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.

  
Richard J. McDermott, P.E.

  
John E. Gribbin, P.E.



OVERVIEW - CRYSTAL LAKE DAM

31 JANUARY 1981

## TABLE OF CONTENTS

|   | <u>Page</u> |
|---|-------------|
| ASSESSMENT OF GENERAL CONDITION OF DAM  | i           |
| OVERVIEW PHOTO                          | iii         |
| TABLE OF CONTENTS                       | iv          |
| PREFACE                                 | vi          |
| SECTION 1 - PROJECT INFORMATION         | 1           |
| 1.1 General                             |             |
| 1.2 Description of Project              |             |
| 1.3 Pertinent Data                      |             |
| SECTION 2 - ENGINEERING DATA            | 7           |
| 2.1 Design                              |             |
| 2.2 Construction                        |             |
| 2.3 Operation                           |             |
| 2.4 Evaluation                          |             |
| SECTION 3 - VISUAL INSPECTION           | 9           |
| 3.1 Findings                            |             |
| SECTION 4 - OPERATIONAL PROCEDURES      | 12          |
| 4.1 Procedures                          |             |
| 4.2 Maintenance of Dam                  |             |
| 4.3 Maintenance of Operating Facilities |             |
| 4.4 Description of Warning System       |             |
| 4.5 Evaluation                          |             |

TABLE OF CONTENTS (cont.)

|  | <u>Page</u> |
|--|-------------|
| SECTION 5 - HYDRAULIC/HYDROLOGIC           | 14          |
| 5.1 Evaluation of Features                 |             |
| SECTION 6 - STRUCTURAL STABILITY           | 16          |
| 6.1 Evaluation of Structural Stability     |             |
| SECTION 7 - ASSESSMENT AND RECOMMENDATIONS | 18          |
| 7.1 Dam Assessment                         |             |
| 7.2 Recommendations                        |             |
| PLATES                                     |             |
| 1 KEY MAP                                  |             |
| 2 VICINTIY MAP                             |             |
| 3 SOIL MAP                                 |             |
| 4 GENERAL PLAN                             |             |
| 5 SECTIONS                                 |             |
| 6 PHOTO LOCATION PLAN                      |             |
| APPENDICES                                 |             |
| 1 Check List - Visual Inspection           |             |
| Check List - Engineering Data              |             |
| 2 Photographs                              |             |
| 3 Engineering Data                         |             |
| 4 Hydraulic/Hydrologic Computations        |             |
| 5 Bibliography                             |             |

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that the unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydraulic and hydrologic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydraulic and hydrologic studies, considering the size of the dam, its general condition and the downstream damage potential.

# PHASE I INSPECTION REPORT

## NATIONAL DAM SAFETY PROGRAM

CRYSTAL LAKE DAM, I.D. NJ00299

### SECTION 1: PROJECT INFORMATION

#### 1.1 General

##### a. Authority

Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspections throughout the United States. The Division of Water Resources of the New Jersey Department of Environmental Protection (NJDEP) in cooperation with the Philadelphia District of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the State of New Jersey. Storch Engineers has been retained by the NJDEP to inspect and report on a selected group of these dams. The NJDEP is under agreement with the Philadelphia District of the Corps of Engineers.

##### b. Purpose of Inspection

The visual inspection of Crystal Lake Dam was made on January 6, 1981. The purpose of the inspection was to make a general assessment of the structural integrity and operational adequacy of the dam structure and its appurtenances.

## 1.2 Description of Project

### a. Description

The dam consists of an earth embankment supporting N.J. Highway Route 130. The spillway structure consists of a horseshoe-shaped concrete and steel interlocking sheet pile weir located on the upstream side of the embankment. At the center of the embankment a concrete bridge forms the spillway discharge channel.

The outlet works consists of a gated 2' x 2' sluice which transversely penetrates the center of the concrete spillway structure.

The crest of the dam is stabilized by the paved roadway of Route 130 and a heavy stand of grass. Portions of the upstream and downstream sides of the embankment near the bridge are stabilized by concrete and bituminous pavement.

The elevation of the spillway crest is 5.7, National Geodetic Vertical Datum (N.G.V.D.) while that of the crest of dam is 13.2. The elevation of the invert of the outlet works is 2.7 while that of the channel bed is 0.3. The overall length of the dam is 500 feet and its height is 12.9 feet. The top width of the dam is 75 feet and the side slopes are 2 horizontal to 1 vertical.

### b. Location

Crystal Lake Dam is located in the Townships of Bordentown and Mansfield, Burlington County, New Jersey. It impounds a recreational lake located adjacent to Route 130. Principal access to the dam is Route 130 which traverses the crest. Discharge from the spillway of the dam flows into a tributary of the Delaware River.



c. Size and Hazard Classification

The dam is classified in accordance with criteria presented in "Recommended Guidelines for Safety Inspection of Dams" published by the U.S. Army Corps of Engineers. Size categories consist of Small, Intermediate and Large while hazard categories are designated as Low, Significant and High.

Size Classification: Crystal Lake Dam is classified as "Small" size since its maximum storage volume is 441 acre-feet (which is less than 1000 acre-feet) and its height is 12.9 feet (which is less than 40 feet).

Hazard Classification: Visual inspection of the downstream flood plain of the dam indicates that failure of the dam could damage the roadway of NJ Route 130 which traverses the crest of the embankment and the railroad embankment located 200 feet from the dam. However, the size of embankment and anticipated high tailwater during a storm equivalent to the SDF reduces the probability of a breach. Accordingly, Crystal Lake Dam is classified as "Significant" hazard.

d. Ownership

Crystal Lake Dam is owned and operated by the State of New Jersey, Department of Transportation, 1035 Parkway Avenue, Trenton, N.J. 08625. The impoundment, Crystal Lake, is owned by the Realty Transfer Co., 1 Elizabeth Plaza, Elizabeth, N.J. 07207.

e. Purpose of Dam

The purpose of the dam is the impoundment of a private recreational lake facility.

f. Design and Construction History

Reportedly, the present concrete horseshoe spillway structure at Crystal Lake Dam was constructed around 1940, replacing the old timber stoplog spillway. This spillway modification was initiated because of the flood of August 23, 1938 which overtopped the road embankment. The work was accomplished by the New Jersey State Highway Department.

Reportedly, no records or plans for the construction of the original dam are on file.

Dam Application No. 337 was issued to the New Jersey State Highway Department by the State Water Policy Commission on October 18, 1939 for the construction of a new spillway.

g. Normal Operational Procedures

The dam and appurtenances are maintained by the New Jersey Department of Transportation Maintenance Division. There is no fixed schedule of maintenance; repairs are made as the need arises.

The outlet works has been used to drain the lake for lake maintenance purposes, usually on request from the owner of the impoundment. It is not known when the lake was last lowered.

1.3 Pertinent Data

a. Drainage area 3.81 square miles

b. Discharge at Damsite

Maximum flood at damsite July 23, 1938 (Roadway overtopped) Inflow quantity unknown.

|                                 |             |
|---------------------------------|-------------|
| Outlet works at pool elevation  | 20 c.f.s.   |
| Spillway capacity at top of dam | 1350 c.f.s. |

c. Elevation (N.G.V.D.)

|                                 |  |
|---------------------------------|--|
| Top of Dam                      | 13.2   |
| Maximum pool-design surcharge   | 13.2   |
| Recreation pool                 | 5.7  |
| Spillway crest                  | 5.7  |
| Stream bed at centerline of dam | 0.3  |
| Maximum tailwater               | 15 (Estimated)   |
|                                 | (Normal tailwater<br>varies with tidal<br>fluctuations.) |

d. Reservoir

|                           |                       |
|---------------------------|-----------------------|
| Length of maximum pool    | 4000 feet (Estimated) |
| Length of recreation pool | 2400 feet (Scaled)    |

e. Storage (Acre-feet)

|                  |     |
|------------------|-----|
| Recreation pool  | 50  |
| Design surcharge | 441 |
| Top of dam       | 441 |

f. Reservoir Surface (acres)

|  |                  |
|--|------------------|
| Top of dam                             | 78.3 (Estimated) |
| Maximum Pool Design - design surcharge | 90.0 (Estimated) |
| Recreation Pool                        | 27.6             |

g. Dam

|        |           |
|--------|-----------|
| Type   | Earthfill |
| Length | 500 feet  |

|                       |                     |
|-----------------------|---------------------|
| Height                | 12.9 feet           |
| Sideslopes - Upstream | 2 horiz. to 1 vert. |
| - Downstream          | 2 horiz. to 1 vert. |
| Zoning                | Unknown             |
| Impervious core       | Unknown             |
| Cutoff                | Unknown             |
| Grout curtain         | Unknown             |

h. Diversion and Regulating Tunnel N.A.

i. Spillway

|                    |                             |
|--------------------|-----------------------------|
| Type               | Concrete Weir               |
| Length of weir     | 36.0 feet                   |
| Crest elevation    | 5.7                         |
| Gates              | N.A.                        |
| Upstream channel   | N.A.                        |
| Downstream channel | 12.5' x 8.8' Bridge Opening |

j. Regulating Outlet

2' x 2' low-level outlet sluice controlled by slide gate

## SECTION 2: ENGINEERING DATA

### 2.1 Design

No plans or calculations pertaining to the original construction of the dam could be obtained. Drawings and calculations prepared in or about 1938 relating to the construction of the present spillway structure which shown plans of the spillway and appurtenant structures are available in the files of the NJDEP, Division of Water Resources.

Design flood peak flow was computed to be 783 c.f.s. based on the Central Jersey Curve. Hydraulic analysis indicated that the spillway and bridge could pass 894 c.f.s. with a free board of 2 feet.

### 2.2 Construction

No data or reports pertaining to the original construction of the dam are available. Construction data or reports are limited to a final acceptance report, dated June 24, 1944 for the construction of the present spillway structure.

### 2.3 Operation

Reportedly, informal maintenance reports are on file with the NJDOT Maintenance Division pertaining to spillway and bridge. No data pertaining to operations are available.

### 2.4 Evaluation

#### a. Availability

Available engineering data is limited to that which is on file with the NJDEP and NJDOT. These files contain plans and calculations relating to the present spillway structure and appurtenances.

b. Adequacy

Available engineering data pertaining to Crystal Lake Dam is of limited assistance to the performance of a Phase I evaluation. A list of absent information is included in paragraph 7.1.b.

c. Validity

The available hydraulic analyses appear to be valid with respect to engineering practice generally accepted in 1938. However, they are not valid according to analytic procedures developed by the Corps of Engineers for the present inspection and assessment program.

Although spillway discharge rates are in close agreement with values computed in connection with this Phase I Report, the design flood used in 1938 is not in conformance with the presently utilized SDF.

## SECTION 3: VISUAL INSPECTION

### 3.1 Findings

#### a. General

The inspection of Crystal Lake Dam was performed on January 8, 1981 by staff members of Storch Engineers. A copy of the visual inspection check list is contained in Appendix 1. The following procedures were employed for the inspection:

- 1) The embankment of the dam, appurtenant structures and adjacent areas were examined.
- 2) The embankment and accessible appurtenant structures were measured and key elevations determined by surveyor's level.
- 3) The embankment, appurtenant structures and adjacent areas were photographed.

#### b. Dam

The roadway pavement was in satisfactory condition and the grass growth in the median and shoulder areas was thick. Steel guide rails extending for the entire length of the dam on both sides of the roadway appeared to be in satisfactory condition.

The upstream face of the dam was slightly irregular and generally covered with weeds, bushes and trees ranging in caliper from 2 inches to 8 inches. The upstream side of the embankment adjacent to both wingwalls of the bridge structure was stabilized with asphalt which appeared to be in satisfactory condition, however, some erosion was observed just beyond the limit of the asphalt. In addition, there was evidence of some riprap on the upstream face of the dam, but it appeared to be inadequate.

The downstream face of the dam appeared to be more regularly graded than the upstream face, and was covered with weeds, some bare spots and many small trees that had been cut off approximately 1 foot above the ground line. The areas adjacent to both sides of the bridge were stabilized by concrete debris that appeared to have been hand placed as riprap. To the left and right of the riprap were two concrete flumes that stabilized the soil and allowed surface water to run off the roadway and into the downstream stilling basin. Some concrete riprap at the toe of the dam on the right side of the bridge appeared to be dislodged. The concrete debris forming the riprap appeared to have been grouted in place. On the left side of the bridge the pieces of concrete were not grouted but simply hand placed.

c. Appurtenant Structures

The spillway crest was in the shape of a broad crested weir and was formed by two parallel rows of interlocking steel sheet piling. The sheet piling appeared to be sound and in generally satisfactory condition. The sheet piling extended from within the embankment on the left side, around the horse-shoe to within the embankment on the right side. The concrete spillway discharges onto a concrete apron which joins the downstream channel formed by the bridge opening.

The concrete railings on both the upstream and downstream headwalls for the bridge appeared to be in satisfactory condition. The downstream wingwalls appeared to be generally sound with the top, or cap, of the right wingwall cracked and spalled at its downstream end. The left wingwall appeared to be in satisfactory condition.

The wingwalls and the concrete surfaces on the upstream end of the bridge appeared, generally, to be in satisfactory condition. There were a few hairline cracks with a small amount of exudation present on the upstream wingwalls and on the concrete surfaces of the bridge abutments.



Two corrugated metal pipes were observed protruding from the embankment immediately to the left of the spillway on the upstream side. The smaller of the two did not appear to have an observable intake end and could possibly be a toe drain. The larger of the two was in poor condition, being significantly rusted with some of the surface rusted through and with no observable inlet structure on the road. An additional corrugated metal pipe was observed on the right side about 10 feet from the spillway and appeared to be in satisfactory condition.

The low level outlet sluice gate mechanism was not operated at the time of inspection and appeared rusty but intact.

d. Reservoir Area

The impoundment of the dam is 2400 feet long with a width varying from 300 feet to 600 feet. The lake shores are thickly wooded with shore slopes of approximately 40 percent on the left side and more moderate slopes of 5 percent to 10 percent on the right side.

e. Downstream Channel

The spillway discharges into a tributary of the Delaware River.

Approximately 200 feet downstream from the dam there is a railroad constructed on an embankment running approximately parallel to the dam. There is a bridge opening in the embankment through which the downstream channel flows. Between the dam and the railroad embankment there is a large pool forming a stilling basin for the dam. Beyond or downstream from the railroad embankment the downstream channel is a broad, sluggish stream, wooded along the banks with an industrial yard on its right side.

## SECTION 4: OPERATIONAL PROCEDURES

### 4.1 Procedures

The level of water in Crystal Lake is regulated by discharge over the concrete spillway. Reportedly, the outlet works of the dam is not currently used to drain the lake or to augment the discharge capacity of the spillway. It is not known when the lake was last drawn down.

The tailwater elevation normally varies in accordance with tidal fluctuations.

### 4.2 Maintenance of the Dam

Reportedly, maintenance is performed on an "as needed" basis. The NJDOT Maintenance Department maintains the shoulder of the roadway on the crest of the dam and reportedly does not maintain the upstream or downstream embankments of the dam.

### 4.3 Maintenance of Operating Facilities

It is not known if the operating mechanism for the outlet works currently functions properly. Reportedly, the outlet is not currently maintained.

### 4.4. Description of Warning System

Reportedly, no warning system is currently in use for the dam.

### 4.5 Evaluation of Operational Adequacy

The operation of the dam has been successful to the extent that the dam reportedly has not been overtopped since the construction of the new spillway in 1940. Reportedly, the dam (roadway) was overtopped during the flood of July 23, 1938.

Although maintenance has been adequate in some areas, some aspects of dam maintenance have not been satisfactorily performed, including the following:

- 1) Outlet works facilities not maintained.
- 2) Spalled concrete and cracks on wingwalls not repaired.
- 3) Trees on upstream face of embankment not removed.
- 4) Eroded areas adjacent to upstream end of bridge not stabilized.
- 5) Deteriorated pipes protruding from upstream face not repaired or replaced.
- 6) Dislodged concrete riprap on upstream face not replaced.

## SECTION 5: HYDRAULIC/HYDROLOGIC

### 5.1 Evaluation of Features

#### a. Design Data

The quantity of storm water runoff that the spillway should be able to handle is based on the size and hazard classification of the dam. This runoff quantity called the spillway design flood (SDF) is described in terms of return frequency or probable maximum flood (PMF) depending on the extent of the dam's size and potential hazard. According to the "Recommended Guidelines for Safety Inspection of Dams" published by the U.S. Army Corps of Engineers, the SDF for Crystal Lake Dam falls in a range of 100-year frequency to 1/2 PMF. In this case, the low end of the range, 100-year frequency is chosen since the factors used to select size and hazard classification are on the low side of their respective ranges.

The SDF peak computed for Crystal Lake Dam is 2613 c.f.s. This value is derived from the PMF flood hydrograph computed by the use of the HEC-1-DAM Flood Hydrograph Computer Program using the Soil Conservation Service triangular unit hydrograph with curvilinear transformation. Hydrologic computations and computer output are contained in Appendix 4.

The spillway discharge rates were computed by the use of a weir formula appropriate for the configuration of the spillway structure. The total spillway discharge with lake level equal to the top of the dam was computed to be 1350 c.f.s. The SDF was routed through the dam by use of the HEC-1-DAM computer program using the modified Puls Method. In routing the SDF, it was found that the dam crest would not be overtopped with 0.2 foot of freeboard remaining. Accordingly, the subject spillway is assessed as being adequate in accordance with criteria developed by the U.S. Army Corps of Engineers.

b. Experience Data

Reportedly, the dam has not been overtopped since its new spillway construction in 1940, but was overtopped during the flood of July 23, 1938.

Also, Condition 10 of the permit to reconstruct the spillway, issued in 1939, stated: "Applicant recognizes that spillway will be drowned out by larger floods in Delaware River."

c. Visual Observation

No evidence was found at the time of inspection that would indicate that the dam had been overtopped.

d. Overtopping Potential

According to the hydraulic and hydrologic analyses, a storm of intensity equivalent to the SDF will pass through the spillway with a minimum freeboard of 0.2 foot.

e. Drawdown Data

Drawdown of the lake is accomplished by opening the low level sluice gate. Total time for drawdown is estimated to be 28 hours. (See Appendix 4.) However, the amount of drawdown depends on tidal influenced fluctuations of the tailwater.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability

#### a. Visual Observations

The dam appeared, at the time of inspection to be outwardly structurally sound with no evidence of embankment cracks or distress. The erosion that was observed near the upstream wingwall on the left side of the spillway and the hairline cracks observed in the bridge structure does not appear to be an indication of distress in the dam.

#### b. Generalized Soils Description

The generalized soils description of the site consists of a discontinuous mantle of unconsolidated, stratified alluvial deposits, composed of silty sand and gravel overlying stratified deposits mostly of marine origin. The marine deposits are composed of clay with varying amounts of silt and sand. Depth to bedrock is greater than 100 feet.

#### c. Design and Construction Data

Analysis of structural stability and construction data for the embankment are not available.

#### d. Operating Records

No operating records are available for the dam. The water level of Crystal Lake is not monitored.

e. Post-Construction Changes

Reportedly, post-construction changes have been limited to the construction of the new spillway and outlet works in 1940 which are on file with the NJDEP and NJDOT.

f. Seismic Stability

Crystal Lake Dam is located in Seismic Zone 1 as defined in "Recommended Guidelines for Safety Inspection of Dams" which is a zone of very low seismic activity. Experience indicates that dams in Seismic Zone 1 will have adequate stability under seismic loading conditions if they have adequate stability under static loading conditions. Crystal Lake Dam appeared to be stable at the time of inspection.

## SECTION 7: ASSESSMENT AND RECOMMENDATIONS

### 7.1 Dam Assessment

#### a. Safety

Based on hydraulic and hydrologic analyses outlined in Section 5 and Appendix 4, the spillway of Crystal Lake Dam is assessed as being adequate. The spillway is able to pass the SDF without an overtopping of the dam.

The embankment appeared, at the time of inspection, to be generally outwardly stable. Observed minor erosion and hairline cracks in the bridge structure are not considered evidence of dam instability.

#### b. Adequacy of Information

Information sources for this report include 1) field inspections, 2) USGS quadrangle, 3) consultation with personnel of the Realty Transfer Company and 4) consultation and information on file with the NJDEP and NJDOT. The information obtained is sufficient to allow a Phase I assessment as outlined in "Recommended Guidelines for Safety Inspection of Dams."

Some of the absent data are as follows:

1. Description of fill material for embankment.
2. Soils report for the site.
3. Design report.

#### c. Necessity for Additional Data/Evaluation

Although some data pertaining to Crystal Lake Dam are not available, additional data are not considered imperative for this Phase I evaluation.



## 7.2 Recommendations

### a. Remedial Measures

Based on hydraulic and hydrologic analyses outlined in paragraph 5.1.a, the spillway is considered to be adequate.

The owner should, in the near future, develop an emergency action plan together with an effective warning system outlining actions to be taken by the operator to minimize downstream effects of an emergency at the dam.

In addition, it is recommended that the following remedial measures be undertaken by the owner in the near future.

- 1) The outlet works should be investigated with respect to operational adequacy and, if necessary, restored to proper operational condition.
- 2) Rusted CMP surface drain pipe should be replaced by proper inlet and pipe.
- 3) Erosion of the embankment adjacent to the upstream wingwalls of the bridge should be properly stabilized.
- 4) Deteriorating riprap on the upstream and downstream faces of embankment should be repaired where necessary.
- 5) All trees and adverse vegetation on the embankment should be removed.

### b. Maintenance

In the future, the owner of the dam should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.

PLATES

CRYSTAL LAKE DAM




PLATE 1

STORCH ENGINEERS  
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES  
N.J. DEPT. OF ENVIR. PROTECTION  
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS  
**KEY MAP**  
CRYSTAL LAKE DAM

SCALE: NONE  
DATE: FEB 1981





PLATE 2

STORCH ENGINEERS  
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES  
N.J. DEPT. OF ENVIR. PROTECTION  
TRENTON, NEW JERSEY

# INSPECTION AND EVALUATION OF DAMS VICINITY MAP CRYSTAL LAKE DAM

SCALE: AS SHOWN  
DATE: FEB. 1981



# Legend

- AR Recent alluvium deposited adjacent to present stream courses.
- AM-4 Unconsolidated stratified alluvial material
- M-67 Stratified deposits of marine origin

Note: Information taken from Rutgers University, Soil Survey of New Jersey, Report No. 20, Burlington County, May 1955 and Geologic Map of New Jersey prepared by J.V. Lewis and H. Kummel 1910-1912, revised by H.B. Kummel 1931 and M. Johnson 1950.

PLATE 3

STORCH ENGINEERS  
FLORHAM PARK, NEW JERSEY.


DIVISION OF WATER RESOURCES  
N.J. DEPT. OF ENVIR. PROTECTION  
TRENTON, NEW JERSEY.

INSPECTION AND EVALUATION OF DAMS

SOIL MAP  
CRYSTAL LAKE DAM

SCALE: NONE

DATE: FEB. 1981



*Note Information taken from field  
Inspection January 6, 1981.*





PLATE 4

CRYSTAL LAKE

STORCH ENGINEERS  
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES  
N.J. DEPT. OF ENVIR. PROTECTION  
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS  
GENERAL PLAN  
CRYSTAL LAKE DAM

ID NJ 00299

SCALE: NOT TO SCALE

DATE: FEB. 1981

Bridge Wingwall

Crest of Spillway  
Elev 5.7

Gate Operating  
Mechanism

Lake Water Level  
Elev. 5.7


2' x 2' Sluice

Interlocking Steel  
Sheet Piling


SPILLW

Lake Water Level  
Elev 5.7


TYPIC







## SPILLWAY SECTION



## TYPICAL DAM SECTION

PLATE 5

STORCH ENGINEERS  
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES  
N.J. DEPT. OF ENVIR. PROTECTION  
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS

SECTIONS


CRYSTAL LAKE DAM

I.D. N.J. 00299


SCALE: NOT TO SCALE

DATE: FEB 1981

# Stillling Basin



Note Information taken from field inspection January 6, 1981



TAL LAKE

PLATE 6

|   |  |
|---|--|
| <p>STORCH ENGINEERS<br/>FLORHAM PARK, NEW JERSEY</p>                                  | <p>DIVISION OF WATER RESOURCES<br/>N.J. DEPT. OF ENVIR. PROTECTION<br/>TRENTON, NEW JERSEY</p> |
| <p>INSPECTION AND EVALUATION OF DAMS<br/>PHOTO LOCATION PLAN<br/>CRYSTAL LAKE DAM</p> |  |
| <p>I.D.N.J. 00299</p>   | <p>SCALE: NOT TO SCALE<br/>DATE: FEB. 1981</p>   |

12

APPENDIX 1

Check List - Visual Inspection

Check List - Engineering Data

Check List

Visual Inspection

Phase I

Name of Dam Crystal Lake Dam County Burlington State N.J. Coordinators NJDEP

Date(s) Inspection 1/6/81 Weather Cloudy Temperature 25°F

Pool Elevation at time of Inspection 5.7 M.S.L. Tailwater at Time of Inspection 4.6 M.S.L.

Inspection Personnel:

|                        |                          |
|------------------------|--------------------------|
| <u>John Gribbin</u>    | <u>Richard McDermott</u> |
| <u>Daniel Buckelew</u> | <u></u>                  |
| <u>Mark Brady</u>      | <u></u>                  |

John Gribbin Recorder

# EMBANKMENT

| VISUAL EXAMINATION OF                                 | OBSERVATIONS  | REMARKS OR RECOMMENDATIONS   |
|---|---|--|
| GENERAL   | Paved highway on crest (Rt. 130) in satisfactory condition. Bushes, weeds and trees (2"-8") on upstream face. Trees on downstream face have been cut off approx. 1 foot from ground. Steel guide rails in good condition. | Trees should be removed.   |
| JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM | Junctions appear sound. Some surface erosion observed. See "Erosion" next sheet.  |  |
| ANY NOTICEABLE SEEPAGE                                | None observed.  |  |
| STAFF GAGE AND RECORDER                               | None observed.  |  |
| DRAINS  | Inlets and pipes to convey surface runoff from road, in generally satisfactory condition. However, one CMP severely rusted.   | Rusted CMP surface drain pipe should be replaced by proper inlet and pipe. |

# EMBANKMENT

| VISUAL EXAMINATION                                     | OBSERVATIONS   | REMARKS OR RECOMMENDATIONS   |
|--|--|--|
| SURFACE CRACKS   | None observed.   |  |
| UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE      | None observed.   |  |
| SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES | Upstream face slightly irregular in alignment; possibly due to wave erosion. Erosion from surface runoff observed adjacent to left, upstream wingwall of bridge.             | Embankment stabilization adjacent to bridge should be renovated.   |
| VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST         | Vertical: generally level.<br>Horizontal: downstream face aligned straight; upstream face slightly irregular.  |  |
| RIPRAP   | Riprap on upstream face (12" stones) generally not adequate. Grouted riprap adjacent to right downstream wingwall of bridge generally adequate with some broken away at toe. | Upstream riprap should be renovated by adding more complete cover. Grouted riprap on downstream face should be renovated where required. |

# OUTLET WORKS

| VISUAL EXAMINATION OF                  | OBSERVATIONS   | REMARKS OR RECOMMENDATIONS |
|--|--|----------------------------|
| CONCRETE SURFACES IN<br>OUTLET CONDUIT | Submerged--could not be observed.  |                            |
| INTAKE STRUCTURE                       | Not observed   |                            |
| OUTLET STRUCTURE                       | Not observed   |                            |
| OUTLET CHANNEL                         | Outlet works discharges into spillway discharge channel.   |                            |
| GATE AND GATE HOUSING                  | Gate not observed. Gate operating mechanism appeared rusty but intact. Mechanism not operated at time of inspection. |                            |



# SPILLWAY

| VISUAL EXAMINATION OF | OBSERVATIONS   | REMARKS OR RECOMMENDATIONS   |
|-----------------------|--|--|
| WEIR                  | Concrete surface and steel sheet piles in generally satisfactory condition.  |  |
| INTAKE CHANNEL        | N.A.   |  |
| DISCHARGE CHANNEL     | Upstream wingwalls and abutments in satisfactory condition, with some hairline cracks observed. Downstream wingwalls generally sound; the cap of the right wingwall cracked and spalled at its downstream end. | Discharge channel formed by concrete bridge abutments and wingwalls. |
| BRIDGE                | Bridge deck appeared to be in satisfactory condition.  | Under side of deck not observed.                                     |
|                       |  |  |

# INSTRUMENTATION

| VISUAL EXAMINATION OF | OBSERVATIONS   | REMARKS OR RECOMMENDATIONS |
|-----------------------|--|----------------------------|
| MONUMENTATION/SURVEYS | USGS monument marked G75 observed on left downstream wingwall of bridge. |                            |
| OBSERVATION WELLS     | None   |                            |
| WEIRS                 | None   |                            |
| PIEZOMETERS           | None   |                            |
| OTHER                 |  |                            |

# RESERVOIR

| VISUAL EXAMINATION OF  | OBSERVATIONS  | REMARKS OR RECOMMENDATIONS |
|------------------------|---|----------------------------|
| SLOPES                 | The lake shores are thickly wooded with shore slopes of approx. 40% on the left side and more moderate slopes of approx. 5% to 10% on the right side. |                            |
| SEDIMENTATION          | Unknown.  |                            |
| STRUCTURES ALONG BANKS | None observed.  |                            |
|                        |   |                            |

# DOWNSTREAM CHANNEL

| VISUAL EXAMINATION OF                       | OBSERVATIONS   | REMARKS OR RECOMMENDATIONS |
|---|--|----------------------------|
| CONDITION<br>(OBSTRUCTION,<br>DEBRIS, ETC.) | Large stilling basin immediately downstream from dam. Discharge from dam enters downstream channel through opening in railroad embankment located approx. 200 feet downstream from dam. Channel flows along railroad embankment approx. 1500 feet to Delaware River. |                            |
| SLOPES                                      | Right bank generally flat with left bank formed by railroad embankment.  |                            |
| STRUCTURES ALONG<br>BANKS                   | Railroad tracks along left bank and industrial complex along right bank.   |                            |
|   |  |                            |

CHECK LIST  
ENGINEERING DATA  
DESIGN, CONSTRUCTION, OPERATION

| ITEM                                   | REMARKS   |
|--|---|
| DAM - PLAN                             | On file with N.J. DEP (Dam Permit #337)                       |
| SECTIONS                               |   |
| SPILLWAY - PLAN                        | On file with N.J. DEP and N.J. D.O.T. (Bridge File #0317-159) |
| SECTIONS                               |   |
| DETAILS                                |   |
| OPERATING EQUIPMENT<br>PLANS & DETAILS | On file with N.J. DEP and N.J. D.O.T.                         |
| OUTLETS - PLAN                         | On file with N.J. DEP and N.J. D.O.T.                         |
| DETAILS                                |   |
| CONSTRAINTS                            |   |
| DISCHARGE RATINGS                      |   |
| HYDRAULIC/HYDROLOGIC DATA              | On file with N.J. DEP   |
| RAINFALL/RESERVOIR RECORDS             | Not available   |
| CONSTRUCTION HISTORY                   | On file with N.J. DEP   |
| LOCATION MAP                           | On file with N.J. DEP and N.J. D.O.T.                         |

| ITEM  | REMARKS            |
|---|--------------------|
| DESIGN REPORTS  | Not available      |
| GEOLOGY REPORTS   | Not available      |
| DESIGN COMPUTATIONS<br>HYDROLOGY & HYDRAULICS<br>DAM INSTABILITY<br>SEEPAGE STUDIES | On file with NJDEP |
| MATERIALS INVESTIGATIONS<br>BORING RECORDS<br>LABORATORY<br>FIELD                   | Not available      |
| POST-CONSTRUCTION SURVEYS OF DAM  | Not available      |
| BORROW SOURCES  | Not available      |

| ITEM  | REMARKS   |
|---|---|
| MONITORING SYSTEMS  | Not available   |
| MODIFICATIONS   | Spillway modification, on file with NJDEP                       |
| HIGH POOL RECORDS   | Dam overtopped during flood of July 23, 1938 on file with NJDEP |
| POST CONSTRUCTION ENGINEERING<br>STUDIES AND REPORTS        | Not available   |
| PRIOR ACCIDENTS OR FAILURE OF DAM<br>DESCRIPTION<br>REPORTS | Not available   |
| MAINTENANCE<br>OPERATION<br>RECORDS                         | Informal reports on file with NJDOT                             |

APPENDIX 2

Photographs





PHOTO 1  
SPILLWAY - LOOKING FROM RIGHT



PHOTO 2  
SPILLWAY - LOOKING FROM LEFT

CRYSTAL LAKE DAM  
6 JANUARY 1981




PHOTO 3  
UPSTREAM END OF BRIDGE




PHOTO 4  
DOWNSTREAM END OF BRIDGE

CRYSTAL LAKE DAM  
6 JANUARY 1981




PHOTO 5  
UPSTREAM FACE OF DAM



PHOTO 6  
DOWNSTREAM FACE OF DAM

CRYSTAL LAKE DAM  
6 JANUARY 1981



PHOTO 7

BITUMINOUS SLOPE PROTECTION ADJACENT  
TO RIGHT, UPSTREAM END OF BRIDGE




PHOTO 8

BITUMINOUS SLOPE PROTECTION ADJACENT  
TO LEFT, UPSTREAM END OF BRIDGE.  
CORRUGATED METAL DRAINS IN FOREGROUND

CRYSTAL LAKE DAM  
6 JANUARY 1981



PHOTO 9

CONCRETE SLOPE PROTECTION ADJACENT  
TO RIGHT, DOWNSTREAM END OF BRIDGE



PHOTO 10

CONCRETE SLOPE PROTECTION ADJACENT TO LEFT,  
DOWNSTREAM END OF BRIDGE

CRYSTAL LAKE DAM  
6 JANUARY 1961

APPENDIX 3

Engineering Data

CHECK LIST  
HYDROLOGIC AND HYDRAULIC DATA  
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: Farmland and Wooded

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 5.70 (50 acre-feet)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): N/A

ELEVATION MAXIMUM DESIGN POOL: 13.2

ELEVATION TOP DAM: 13.2

SPILLWAY CREST: Uncontrolled Weir

a. Elevation 5.7

b. Type Broad Crested Weir (Horseshoe Shape)

c. Width 2.5 feet

d. Length 36.0 feet

e. Location Spillover Upstream Side of Dam

f. Number and Type of Gates N.A.

OUTLET WORKS: 2' x 2' Gated Sluice

a. Type Submerged Orifice

b. Location Center of Spillway Weir

c. Entrance Invert 2.7

d. Exit Invert 2.7

e. Emergency Draindown Facilities: Open Gate

HYDROMETEOROLOGICAL GAGES: None

a. Type N/A

b. Location N/A

c. Records N/A

MAXIMUM NON-DAMAGING DISCHARGE:

(Lake Stage Equal to Top of Dam) 1350 c.f.s.

APPENDIX 4

Hydraulic/Hydrologic Computations



HYDROLOGY:HYDROLOGIC ANALYSIS

THE RUNOFF HYDROGRAPH WILL BE DEVELOPED  
BY THE HEC-1-DAM COMPUTER PROGRAM  
USING THE SCS METHOD WITH CURVILINEAR  
TRANSFORMATION

DRAINAGE AREA = 3.81 SQ MI

INFILTRATION DATA

INITIAL INFILTRATION = 1.5 inches

CONSTANT INFILTRATION = 0.15 inches/hour

TIME OF CONCENTRATION

1. [by SCS - TR 55]

OVERLAND FLOW :

$$\text{length} = 4.500 \text{ [Ft]}$$

$$\text{ave. slope} = 1.1 \text{ [%]}$$

$$\Delta H = 110' - 60' = 50'$$

$$\text{ave. velocity} = 0.26 \text{ [F.p.s]}$$

CHANNEL FLOW :

$$\text{length} = 12.500 \text{ [Ft]}$$

$$\text{ave. slope} = 0.4 \text{ [%]}$$

$$\Delta H = 60' - 8' = 52'$$

$$\text{ave velocity} = 2.2 \text{ [F.p.s]}$$

$$T_c = \left[ \left( \frac{4.500}{0.26} \right) + \left( \frac{12.500}{2.2} \right) \right] \frac{1}{3600} = 4.8 + 1.6$$

$$\underline{T_c = 6.4 \text{ Hr.}}$$

2. ['Handbook of applied hydrology' by Chow - Pg 14-36]

$$T_c = 2.14 \sqrt{\frac{2}{3} L \eta / \sqrt{s}}$$

$$T_c = 2.14 \sqrt{\frac{2}{3} (4500 \times 0.4) / \sqrt{0.011}}$$

T<sub>c</sub> = time of concentration [min]

s = slope [%]

η = 0.4 roughness coefficient

L = length of overland flow [Ft]

$$T_c = 78.42 \text{ min} = 1.3 \text{ Hr.}$$

$$T_c = 1.3 + 1.6 = \underline{\underline{2.9 \text{ Hr.}}}$$

3. [by 'Design of small dams' Pg 71]

$$T_c = \left( \frac{11.9(L)^3}{H} \right)^{0.385}$$

$T_c$  = time of concentration [Hr]

$$T_c = \left( \frac{11.9 \times (3.22)^3}{102} \right)^{0.385}$$

$L$  = longest watercourse [Mi]

$H$  = elev. difference [Ft]

$$T_c = \underline{\underline{1.7 \text{ Hr.}}}$$

$$L = 3.22 \text{ [Mi]}$$

$$H = 102 \text{ [Ft]}$$

### FOR COMPUTER INPUT

$$\text{LAG TIME} = 60\% T_c = 4.0 \times 0.6$$

$$\underline{\underline{\text{LAG TIME} = 2.4 \text{ Hr.}}}$$

24 HOUR, 100 YEAR RAINSTORM  
DISTRIBUTION  
FOR CRYSTAL LAKE DAM

| TIME<br>(Hr.) | RAIN<br>(in.) |
|---------------|---------------|
| 1             | 0.08          |
| 2             | 0.08          |
| 3             | 0.08          |
| 4             | 0.08          |
| 5             | 0.08          |
| 6             | 0.08          |
| 7             | 0.09          |
| 8             | 0.09          |
| 9             | 0.18          |
| 10            | 0.18          |
| 11            | 0.18          |
| 12            | 0.19          |
| 13            | 0.3           |
| 14            | 0.3           |
| 15            | 0.8           |
| 16            | 3.0           |
| 17            | 0.4           |
| 18            | 0.3           |
| 19            | 0.19          |
| 20            | 0.18          |
| 21            | 0.09          |
| 22            | 0.09          |
| 23            | 0.08          |
| 24            | 0.08          |

Σ 7.20 inches

STORCH ENGINEERS

Project 1132-06

CRYSTAL LAKE DAM

Sheet 5 of 10Made By Ji Hg Date 3-12-81Chkd By JG Date 3/23/81LAKE STORAGE VOLUMEW. S. ELEV. [FT]AREA [Acres]

0.3

0

5.7

27.6

10.0

57.4

20.0

122.6

30.0

185.5

HEC-1-DAM COMPUTER PROGRAM WILL

DEVELOP STORAGE CAPACITY FROM

WATER SURFACE AREAS AND ELEVATIONS.

INFORMATION TAKEN FROM U.S.G.S. QUAD-

RANGLE COLUMBUS &amp; TRENTON EAST, N.J.



HYDRAULICS

THE SPILLWAY AT THE CRYSTAL LAKE DAM IS A CON-

CRETE FREE OVERFLOW BROAD CRESTED WEIR WITH

A CREST ELEV. 5.7 FEET AND WITH AN EFFECTIVE

LENGTH OF 36.0 FEET



DISCHARGE CALCULATION

[Handbook of hydraulics Pg. 5-3]

DISCHARGE WILL BE CALCULATED FROM SPILLWAY  
 CREST ELEV. 5.7 FEET UP TO THE BOTTOM  
 OF THE BRIDGE AT ELEV. 9.1 FEET USING FORMULA

$$Q = CLH^{3/2}$$

$$Q = \text{discharge} \quad [cfs]$$

$$C = \text{coefficient of discharge}$$

$$L = \text{effective length of spillway} [ft]$$

$$H = \text{total head on spillway} [ft]$$

[HCS-Highway culverts Pg 5-21]


AND FROM ELEV. 12.0 FEET AND ABOVE USING BOX  
 CULVRET INLET CONTROL NOMOGRAPH  
 concrete box  $12.5' \times 8.8'$   $\neq L = 95'$

SPILLWAYSTAGE DISCHARGE TABULATION

| H.S.<br>ELEV.<br>[ft.] | Spillway $L = 36.0'$ |      |            | INLET<br>CONTROL<br>Q [cfs] | $\Sigma Q$<br>[cfs] |
|------------------------|----------------------|------|------------|-----------------------------|---------------------|
|                        | H<br>[ft.]           | C    | Q<br>[cfs] |                             |                     |
| 5.7                    | 0                    | 0    | 0          |                             | 0                   |
| 6.0                    | 0.3                  | 2.54 | 15.0       |                             | 15.0                |
| 7.0                    | 1.3                  | 2.66 | 142.0      |                             | 142.0               |
| 8.0                    | 2.3                  | 2.84 | 357.0      |                             | 357.0               |
| 9.1                    | 3.4                  | 3.16 | 713.0      | 750.0                       | 713.0               |
| 10.0                   | 4.3                  | 3.32 | 1065.0     | 938.0                       | 938.0               |
| 11.0                   | 5.3                  | 3.32 | 1458.0     | 1052.0                      | 1052.0              |
| 12.0                   |                      |      |            | 1187.0                      | 1187.0              |
| 13.2                   |                      |      |            | 1350.0                      | 1350.0              |
| 14.0                   |                      |      |            | 1450.0                      | 1450.0              |
| 15.0                   |                      |      |            | 1550.0                      | 1550.0              |
| 16.0                   |                      |      |            | 1650.0                      | 1650.0              |

SPILLWAY  
STAGE DISCHARGE CURVE

SQUARE 4 X 4 TO THE INCH






DRAWDOWN

[Handbook of hydraulics, Pg 4-11]

THE DRAWDOWN DISCHARGE WILL BE CALCULATED  
FOR SHARP-EDGED (SUBMERGED) ORIFICE WITH  
DIFFERENT WATER SURFACE ELEVATIONS

USING FORMULA:

$C = 0.6$

$Q = C a \sqrt{2g \Delta h}$

$Q = \text{discharge [cfs]}$

$a = 2' \times 2' = 4 \text{ ft}^2$

$C = \text{coefficient of discharge}$

$\Delta h = h_1 - h_2 = 1.1'$

$Q = 0.6 \times 4 \sqrt{2 \times 32.2 \times 1.1}$

$g = 32.2$

$Q = 20.0 \text{ cfs}$

$a = \text{area of discharge [ft}^2\text{]}$

$\Delta h = \text{difference of heads to centroid [ft]}$

$h_1 = 2.0'$

$Q_{\text{TOTAL}} = 0.6 \times 4 \sqrt{32.2 \times 2 \times 2.0}$

$Q_{\text{TOTAL}} = 27.0 \text{ cfs}$

STORCH ENGINEERS

Sheet 10 of 10Project 1132-06CRYSTAL LAKE DAMMade By JiHa Date 3-12-81Chkd By JG Date 3/23/81TIME OF DRAWDOWN

$$T_d = \frac{\text{Storage [Acft]}}{\text{Ave. discharge - inflow [cfs]}} \times \frac{43560}{3600}$$

Assume inflow 5.0 cfs

for  $\Delta h = 1.1'$ 

$$T_d = \frac{50}{20.0 - 5.0} \times \frac{43560}{3600} = \underline{\underline{40}} \text{ [Hr]}$$

for  $h_1 = 2.0'$ 

$$T_d = \frac{50}{27.0 - 5.0} \times \frac{43560}{3600} = \underline{\underline{27.5}} \text{ [Hr]}$$

HEC - 1 - DAM PRINTOUT

Overtopping Analysis

|     |                                       |       |       |       |       |       |       |       |       |       |
|-----|---------------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| IA1 | NATIONAL DAM SAFETY PROGRAM           |       |       |       |       |       |       |       |       |       |
| A2  | CRYSTAL LAKE DAM, NEW JERSEY          |       |       |       |       |       |       |       |       |       |
| A3  | 100 YEAR STORM ROUTING                |       |       |       |       |       |       |       |       |       |
| R   | 300                                   | 0     | 15    | 4     |       |       |       |       |       |       |
| R1  | 5                                     |       |       |       |       |       |       |       |       |       |
| J   | 1                                     | 1     | 1     |       |       |       |       |       |       |       |
| J1  | 1                                     |       |       |       |       |       |       |       |       |       |
| K   | 0                                     | LAKE  | 1     |       |       |       |       |       |       |       |
| K1  | INFLOW HYDROGRAPH TO CRYSTAL LAKE DAM |       |       |       |       |       |       |       |       |       |
| H   | 0                                     | 2     | 3.81  | 3.81  | 1     |       |       |       |       |       |
| O   | 96                                    |       |       |       |       |       |       |       |       |       |
| O1  | 0.019                                 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 |
| O1  | 0.019                                 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 |
| O1  | 0.019                                 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 |
| O1  | 0.019                                 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 |
| O1  | 0.019                                 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.019 | 0.038 | 0.038 |
| O1  | 0.038                                 | 0.038 | 0.038 | 0.038 | 0.038 | 0.038 | 0.038 | 0.038 | 0.038 | 0.038 |
| O1  | 0.083                                 | 0.083 | 0.083 | 0.083 | 0.163 | 0.163 | 0.163 | 0.163 | 0.750 | 0.750 |
| O1  | 0.750                                 | 0.750 | 0.163 | 0.163 | 0.163 | 0.163 | 0.083 | 0.083 | 0.083 | 0.083 |
| O1  | 0.083                                 | 0.083 | 0.083 | 0.083 | 0.038 | 0.038 | 0.038 | 0.038 | 0.038 | 0.038 |
| O1  | 0.038                                 | 0.038 | 0.038 | 0.038 | 0.038 | 0.038 |       |       |       |       |
| T   |                                       |       |       |       |       |       | 1.5   | 0.15  |       |       |
| W2  | 2.4                                   |       |       |       |       |       |       |       |       |       |
| X   | -1.0                                  | -0.05 | 2.0   |       |       |       |       |       |       |       |
| K   | 1                                     | DAM   |       |       |       |       |       |       |       |       |
| K1  | ROUTE DISCHARGE THROUGH DAM           |       |       |       |       |       |       |       |       |       |
| Y   |                                       |       | 1     | 1     |       |       |       |       |       |       |
| Y1  | 1                                     |       |       |       |       |       |       |       |       |       |
| Y4  | 5.7                                   | 6.0   | 7.0   | 8.0   | 9.1   | 10.0  | 11.0  | 12.0  | 13.2  | 14.0  |
| Y4  | 15.0                                  | 16.0  |       |       |       |       |       |       |       |       |
| Y5  | 0                                     | 15    | 142   | 357   | 713   | 938   | 1052  | 1187  | 1350  | 1450  |
| Y5  | 1550                                  | 1650  |       |       |       |       |       |       |       |       |
| \$A | 0                                     | 27.6  | 57.4  | 122.6 | 185.5 |       |       |       |       |       |
| \$E | 0.3                                   | 5.7   | 10.0  | 20.0  | 30.0  |       |       |       |       |       |
| \$S | 5.7                                   |       |       |       |       |       |       |       |       |       |
| \$D | 13.2                                  | 2.7   | 1.5   | 478   |       |       |       |       |       |       |
| \$B | 200                                   | 1     | 0.5   | 1.0   | 5.7   | 13.2  |       |       |       |       |
| K   | 99                                    |       |       |       |       |       |       |       |       |       |

NATIONAL DAM SAFETY PROGRAM  
CRYSTAL LAKE DAM, NEW JERSEY  
100 YEAR STORM ROUTING

JOB SPECIFICATION

|       |     |      |      |     |      |       |      |      |        |
|-------|-----|------|------|-----|------|-------|------|------|--------|
| NO    | NHR | NMIN | IDAY | IHR | IMIN | METRC | IPLT | IFRT | INSTAN |
| 300   | 0   | 15   | 0    | 0   | 0    | 0     | 0    | 4    | 0      |
| JUPER |     |      |      |     |      |       |      |      |        |
|       | 5   |      |      | 0   | 0    | 0     |      |      |        |
| LROFT |     |      |      |     |      |       |      |      |        |
|       |     |      |      | 0   | 0    | 0     |      |      |        |
| TRACE |     |      |      |     |      |       |      |      |        |
|       |     |      |      |     |      |       |      |      |        |

MULTI-PLAN ANALYSES TO BE PERFORMED

NPLAN= 1 NRTIO= 1 LRTIO= 1

RTIDS= 1.00

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH TO CRYSTAL LAKE DAM

|       |       |       |       |      |      |       |       |       |
|-------|-------|-------|-------|------|------|-------|-------|-------|
| ISTAQ | ICOMP | IECON | ITAPE | JFLT | JFRT | INAME | ISAME | LOCAL |
| 0     | 0     | 0     | 0     | 0    | 0    | 1     | 1     | 0     |
| LAKE  |       |       |       |      |      |       |       |       |

HYDROGRAPH DATA

|       |      |       |      |       |       |       |       |       |       |
|-------|------|-------|------|-------|-------|-------|-------|-------|-------|
| INHYG | IUNG | TAREA | SNAP | TRSDA | TRSPC | RATIO | ISHOW | ISAME | LOCAL |
| 0     | 2    | 3.81  | 0.00 | 3.81  | 0.00  | 0.000 | 0     | 1     | 0     |

LOSS DATA

|       |      |       |       |       |      |       |       |       |       |       |
|-------|------|-------|-------|-------|------|-------|-------|-------|-------|-------|
| LROFT | STKR | DLTKR | RTIOL | ERAIN | STKS | RTIOK | STRTL | CNSTL | ALSMX | RTIMP |
| 0     | 0.00 | 0.00  | 1.00  | 0.00  | 0.00 | 1.00  | 1.50  | .15   | 0.00  | 0.00  |

UNIT HYDROGRAPH DATA

TC= 0.00 LAG= 2.40

RECESSION DATA

STRTQ= -1.00 ORCSN= -.05 RTIOR= 2.00

MO.DA

END-OF-PERIOD FLOW

|       |       |        |      |      |      |        |       |       |        |      |      |      |        |
|-------|-------|--------|------|------|------|--------|-------|-------|--------|------|------|------|--------|
| MO.DA | HR.MN | PERIOD | RAIN | EXCS | LOSS | COMP R | MO.DA | HR.MN | PERIOD | RAIN | EXCS | LOSS | COMP R |
|-------|-------|--------|------|------|------|--------|-------|-------|--------|------|------|------|--------|

SUN 7.12 4.33 2.79 43762.  
( 181.)( 110.)( 71.)( 1239.20)

# HYDROGRAPH ROUTING

## ROUTE DISCHARGE THROUGH DAM

| ISTAO           | ICOMP   | TECON  | ITAPE  | JPLT   | JFRT   | INAME   | ISTAGE  | IAUTD   |
|-----------------|---------|--------|--------|--------|--------|---------|---------|---------|
| DAM             | 1       | 0      | 0      | 0      | 0      | 0       | 0       | 0       |
| ROUTING DATA    |         |        |        |        |        |         |         |         |
| QLOSS           | CLOSS   | AVG    | IRIS   | ISAME  | IOFT   | IFHF    | LSTR    |         |
| 0.0             | 0.000   | 0.00   | 1      | 1      | 0      | 0       | 0       |         |
| DAM DATA        |         |        |        |        |        |         |         |         |
| HSTFS           | NSTBL   | LAG    | AMSKK  | X      | TSK    | STORA   | ISFRAT  |         |
| 1               | 0       | 0      | 0.000  | 0.000  | 0.000  | -6.     | -1      |         |
| STAGE           |         |        |        |        |        |         |         |         |
| 5.70            | 6.00    | 7.00   | 8.00   | 9.10   | 10.00  | 11.00   | 12.00   | 13.20   |
| 15.00           | 16.00   |        |        |        |        |         |         | 14.00   |
| FLOW            |         |        |        |        |        |         |         |         |
| 0.00            | 15.00   | 142.00 | 357.00 | 713.00 | 938.00 | 1052.00 | 1187.00 | 1350.00 |
| 1550.00         | 1650.00 |        |        |        |        |         |         | 1450.00 |
| SURFACE AREA    |         |        |        |        |        |         |         |         |
| 0.              | 28.     | 57.    | 123.   | 186.   |        |         |         |         |
| CAPACITY        |         |        |        |        |        |         |         |         |
| 0.              | 50.     | 229.   | 1108.  | 2438.  |        |         |         |         |
| ELEVATION       |         |        |        |        |        |         |         |         |
| 0.              | 6.      | 10.    | 20.    | 30.    |        |         |         |         |
| DAM DATA        |         |        |        |        |        |         |         |         |
| TOPEL           | COND    | EXPD   | DAMWID |        |        |         |         |         |
| 13.2            | 2.7     | 1.5    | 478.   |        |        |         |         |         |
| DAM BREACH DATA |         |        |        |        |        |         |         |         |
| BRWID           | Z       | ELEM   | IFAIL  | WSEL   | FAILEL |         |         |         |
| 200.            | 1.00    | .50    | 1.00   | 5.70   | 13.20  |         |         |         |

PEAK OUTFLOW IS 1327. AT TIME 22.00 HOURS

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

| OPERATION          | STATION | AREA  | PLAN RATIO | 1       |
|--------------------|---------|-------|------------|---------|
| HYDROGRAPH AT LAKE | (       | 5.81  | 1          | 2613.   |
|                    | (       |       | (          | 74.00)( |
| ROUTED TO DAM      | (       | 9.87) | 1          | 1327.   |
|                    | (       |       | (          | 37.57)( |

SUMMARY OF DAM SAFETY ANALYSIS

| PLAN 1 ..... |  |  |  | INITIAL VALUE          |  | SPILLWAY CREST        |  | TOP OF DAM          |  |                         |  |                           |  |                       |  |
|--------------|--|--|--|------------------------|--|-----------------------|--|---------------------|--|-------------------------|--|---------------------------|--|-----------------------|--|
| ELEVATION    |  |  |  | 5.70                   |  | 5.70                  |  | 13.20               |  |                         |  |                           |  |                       |  |
| STORAGE      |  |  |  | 50.                    |  | 50.                   |  | 441.                |  |                         |  |                           |  |                       |  |
| OUTFLOW      |  |  |  | 0.                     |  | 0.                    |  | 1350.               |  |                         |  |                           |  |                       |  |
| RATIO OF PMF |  |  |  | MAXIMUM DEPTH OVER DAM |  | MAXIMUM STORAGE AC-FT |  | MAXIMUM OUTFLOW CFS |  | DURATION OVER TOP HOURS |  | TIME OF MAX OUTFLOW HOURS |  | TIME OF FAILURE HOURS |  |
| 1.00         |  |  |  | 0.00                   |  | 428.                  |  | 1327.               |  | 0.00                    |  | 22.00                     |  | 0.00                  |  |
| 13.03        |  |  |  |                        |  |                       |  |                     |  |                         |  |                           |  |                       |  |

APPENDIX 5

Bibliography



1. "Recommended Guidelines for Safety Inspection of Dams," Department of the Army, Office of the Chief of Engineers, Washington, D.C. 20314.
2. Design of Small Dams, Second Edition, United States Department of the Interior, Bureau of Reclamation, United State Government Printing Office, Washington, D.C., 1973.
3. Holman, William W. and Jumikis, Alfreds R., Engineering Soil Survey of New Jersey, Report No. 20, Burlington County, Rutgers University, New Brunswick, N.J., 1955.
4. "Geologic Map of New Jersey," prepared by J. Volney Lewis and Henry B. Kummel, dated 1910-1912, revised by H.B. Kummel, 1931 and M. Johnson, 1950.
5. Chow, Ven Te., Ed., Handbook of Applied Hydrology, McGraw-Hill Book Company, 1964.
6. Herr, Lester A., Hydraulic Charts for the Selection of Highway Culverts, U.S. Department of Transportation, Federal Highway Administration, 1965.
7. Safety of Small Dams, Proceedings of the Engineering Foundation Conference, American Society of Civil Engineers, 1974.
8. King, Horace Williams and Brater, Ernest F., Handbook of Hydraulics, Fifth Edition, McGraw-Hill Book Company, 1963.
9. Urban Hydrology for Small Watersheds, Technical Release No. 55, Engineering Division, Soil Conservation Service, U.S. Department of Agriculture, January 1975.

DATE  
FILMED  
-8